## CITY OF ST. JOHNS

# Fantasy Forest 2.0 Playground Improvements Playground Installation and Sitework





Mayor Scott Dzurka Vice Mayor Brad Gurski Commissioner Chris Hyzer Commissioner Eric Hufnagel Commissioner Chris DeLiso

> Kristina Kinde **TREASURER**

## Chad A. Gamble, P.E.

**CITY MANAGER** 100 E State St, Suite #1100 St Johns, MI 48879 989.224.8944 cgamble@stjohnsmi.gov


## William Schafer


PARKS & RECREATION DIRECTOR 100 E State St, Suite #1100 St Johns, MI 48879 989.224.8944 bschafer@stjohnsmi.gov

## Mindy J. Seavey CLERK

**Justin Smith** 

DIRECTOR OF PUBLIC SERVICES 100 E State St, Suite #1100 St Johns, MI 48879 989.224.8944 jsmith@stjohnsmi.gov






SHEET INDEX			
GENERAL SHEETS	SHEET NO.		
COVER SHEET	G-1.0		
LEGEND & NOTES SHEET	G-2.0		
EXISTING CONDITIONS PLAN	C-1.0		
EXISTING TREE CONDITION ASSESSMENT	C-1.1		
DEMOLITION PLAN	C-2.0		
SOIL EROSION & SEDIMENTATION CONTROL PLAN	C-2.1		
SOIL EROSION & SEDIMENTATION CONTROL DETAILS	C-2.2		
SITE LAYOUT PLAN	C-3.0		
SITE PLAN PLAYGROUND ENLARGEMENT	C-3.1		
GRADING PLAN - NORTH	C-4.0		
GRADING PLAN - SOUTH	C-4.1		
SITE DETAILS	C-5.0		
SITE DETAILS	C-5.1		
LANDSCAPE PLAN	L-1.0		
LANDSCAPE NOTES & DETAILS	L-2.0		
LANDSCAPE DETAILS	L-2.1		

ISSUED FOR BID


DATE BY 01/16/25 CAD

Call before you dig.



CATHERINE A DENNIS. PLA

Know what's below.



STORM SEWER AND DRAINAGE FEATURES	<u>EXISTING</u>	PROPOSED
STORM SEWER TOP OF BANK TOE OF BANK		
DITCH CENTERLINE -		<b>→ → →</b>
ROUND CATCH BASIN	Œ	<b>©</b>
SQUARE CATCH BASIN	CB	CE
ISTERN	O	<b>0</b>
OX CULVERT		Ę
JLVERT HEADWALL JLVERT END SECTION	(	ζ (
OWN SPOUT	<b>⊠</b> DS	ŬDS
OUND INLET	Φ	Φ
QUARE INLET		
FORM MANHOLE	<b>0</b>	<b>⑤</b>
TORM SEWER STUB	⊠ <sub>STS</sub>	
ANITARY SEWER		
ANITARY SEWER -		
PRCEMAIN - LEAN OUT	FMFMFM	• <b>FM FM</b> • CO
JMP STATION MANHOLE	<b>193</b>	<b>©</b>
ANITARY MANHOLE	0	<b>S</b>
EPTIC TANK	\$	
EWER VENT	°SV	o <sub>SV</sub>
NITARY SEWER STUB	⊠ <sub>SANS</sub>	
MESTIC WATER		
TERMAIN CKFLOW PREVENTER		
OW-OFF VALVE		Ō
RE DEPT. CONNECTION		Ŷ
RE HYDRANT	Д	•
TE VALVE & BOX	8	0
TE VALVE & WELL TER PIT	⊘ <b>I</b> ZEP	
TER PIT ST INDICATOR VALVE	<b>м</b> дн Х	мн 8
VE	Δ ⋈	∆ <b>⋈</b>
TER FAUCET	°WF	$\circ_{WF}$
TER METER	°WM	O <sub>WM</sub>
TER SHUT-OFF	₩So	wso
ATER LINE STUB	⊠ <sub>WLS</sub>	0
LL	°WE	OWE
ERHEAD UTILITIES		
ADMAN ANCHOR	<b>°</b> DА	$^{O}_{DA}$
Y WIRE ANCHOR	°GA	$^{O}GA$
Y WIRE POLE	°GP	O <sub>GP</sub>
WER AND LIGHT POLE	Ø	
LE BOX		
LEPHONE, CABLE TV, WER AND LIGHT POLE	дтср	
LEPHONE, CABLE TV	Ø <sub>TCP</sub>	
D POWER POLE		
EPHONE AND CABLE POLE	TO	
EPHONE, CABLE TV D LIGHT POLE	M	
LEPHONE AND LIGHT LE	斑	
LEPHONE, POWER AND SHT POLE	斑	
LEPHONE AND POWER	TD <sup>9</sup>	
LE LITY POLE	Ø	Ø
HTING	~	~
	<b>.</b> ⊁Ł	<b>-</b>
OOD LIGHT MP POLE	₩ X	<b>☆</b> <b>★</b>
TAL LIGHT POLE	)X	<b>X</b>
IAMENTAL LIGHT	×	â
MOLITION		_ <b>.</b>
EE PROTECTION FENCE		<del>* * * * *</del>
MOVAL FEATURE		· <b>X·X·X·X·X·X·X·X·X·X·X·X·X·X·X</b>
MOVAL PAVEMENT		
MOVAL — CONCRETE		
L EROSION CONTROL		
IFENCE —	-//////	<del></del>
ITROL MEASURE	##	
	• •	_

STABILIZED CONSTRUCTION ACCESS

ELECTRICAL	EXISTING	PROPOSED
OVERHEAD —	EE	EE
UNDERGROUND —	——UEUE	UEUE
CIRCUIT BREAKER PANEL	© <sub>CBP</sub>	E <sub>CBP</sub>
HANDHOLE	Δ	
ELECTRIC MANHOLE	Ð	©
ELECTRICAL OUTLET	₽	£
PEDESTAL	EB	PP
TRANSFORMER	E	E
ELECTRIC METER	°EM	<sup>о</sup> ЕМ
POWER POLE POWER TOWER	Ø	Ø
POWER TOWER		
COMMUNICATION/DATA	<b>.</b>	<b>.</b>
OVERHEAD TELEPHONE — U/G TELEPHONE —		
•		
TELEPHONE POLE	Ø	Ø
TELEPHONE MANHOLE	Ф	<b>O</b>
TELEPHONE PEDESTAL	Œ	
CABLE TV		
	CTVCTV	CTVCTV
		- UCTV
CTV POLE	Ø	Ø
CTV PEDESTAL		
GAS AND OIL		
GAS —	GG	GG
OIL —	OIL	GG
VENT	◇VT	<b>Ŷ</b> Ţ
BLOW-OFF	<b>⇔</b> B0	980
FILLER PIPE & RISER	<b>⇔</b> R	<b>∽</b> R
METER	<b>⇔</b> GM	<b>∽</b> GM
GAS MANHOLE	©	•
STOP BOX SHUTOFF VALVE	≎c∨ ≎	♦
GAS WELL	≎GW	<b>⇔</b> GV
U/G GAS TANK	≎GT	
ELECTRIC, CTV AND		E&CTV&T
TELEPHONE		E&CTV
ELECTRIC AND		E&T
TELEPHONE	CTV&T	CTV&T
U /O ELEOTDIO OT/		
AND TELEPHONE	UE&CTV&T	UE&CTV&T
U/G ELECTRIC AND CTV	———UE&CTV———	UE&CTV
U/G ELECTRIC AND TELEPHONE	UE&T	UE&T
U/G CTV AND	I	UCTV&T

.~~~~~~~~~~

-0-0-0-

{ MS }

 $\overline{\phantom{a}}$ 

BRUSH LINE

HEDGE ROW

TREE LINE

WETLANDS

STUMP

TREE DRIPLINE

CONIFEROUS BUSH

CONIFEROUS TREE

DECIDUOUS BUSH

DECIDUOUS TREE

MULTISTEM CONIFEROUS

MULTISTEM DECIDUOUS

#### GENERAL CONSTRUCTION NOTES:

- 1. THREE (3) WORKING DAYS PRIOR TO BEGINNING CONSTRUCTION, IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT MISS DIG UTILITY PROTECTION SERVICE (1-800-482-7171) OR 811 TO VERIFY THE LOCATION OF ALL EXISTING UTILITIES. THE CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR THE PROTECTION OF ALL EXISTING UTILITIES DURING CONSTRUCTION. ALL UTILITIES DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED IN ACCORDANCE WITH THE UTILITY OWNER'S REQUIREMENTS.
- 2. IN CASES WHERE EXISTING SEWERS, DRAINS, GAS SERVICE CONNECTION, TELEPHONE OR ELECTRICAL FACILITIES, AND WATER SERVICE CONNECTIONS ARE ENCOUNTERED, THE CONTRACTOR SHALL PERFORM HIS OPERATIONS IN SUCH A MANNER THAT THE SERVICE WILL BE UNINTERRUPTED AND THE COST THEREOF SHALL BE AT THE CONTRACTOR'S EXPENSE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING HIS CONSTRUCTION OPERATIONS WITH THE USERS OF THE UTILITIES AND UTILITY ITSELF. THE METHODS USED BY THE CONTRACTOR FOR MAINTAINING AND SUPPORTING UTILITIES AND THEIR SERVICE CONNECTIONS SHALL BE SUCH AS TO AVOID SETTLEMENT OF SUCH UTILITIES BEFORE AND AFTER PLACING BACKFILL. SUPPORT DETAILS SHALL MEET THE APPROVAL OF THE UTILITY INVOLVED.
- 3. ALL COST AND FEES CHARGED BY ANY UTILITY (I.E. GAS, ELECTRIC, TELEPHONE, CABLE TV.) PURSUANT TO CONSTRUCTION OF THE SITE IMPROVEMENTS SHALL BE PAID FOR BY THE CONTRACTOR. THIS SHALL INCLUDE, BUT NOT NECESSARILY BE LIMITED TO, TEMPORARY SUPPORT OF POLES; TEMPORARY SUPPORT OF UNDERGROUND PIPE, CONDUITS, AND CABLES; RELOCATION, REPAIR, AND/OR REPLACEMENT OF SERVICE LEADS.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF ALL EXISTING UTILITIES DURING CONSTRUCTION. IF ANY EXISTING UTILITY IS DAMAGED BY THE CONTRACTOR'S OPERATION, IT SHALL BE REPAIRED IN ACCORDANCE WITH THE RELATED UTILITIES STANDARDS AT THE CONTRACTOR'S EXPENSE.
- 5. THE LOCATIONS OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS HAVE BEEN DETERMINED FROM THE BEST INFORMATION AVAILABLE AND ARE PROVIDED FOR THE CONVENIENCE OF THE CONTRACTOR. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THEIR COMPLETENESS OR ACCURACY. PRIOR TO THE START OF ANY DEMOLITION ACTIVITY, THE CONTRACTOR SHALL CONTACT THE UTILITY COMPANIES TO OBTAIN ONSITE LOCATIONS OF EXISTING UTILITIES.
- 6. ALL EXISTING SEWERS, WATER MAIN PIPING AND OTHER UTILITIES SHOWN ARE NOT TO BE INTERPRETED AS THE EXACT LOCATION, OR AS THE ONLY OBSTACLES THAT MAY OCCUR ON THE SITE. VERIFY EXISTING CONDITIONS AND PROCEED WITH CAUTION AROUND ANY ANTICIPATED FEATURES. GIVE NOTICE TO ALL UTILITY COMPANIES REGARDING DESTRUCTION AND REMOVAL OF ALL SERVICE LINES AND CAP ALL LINES BEFORE PROCEEDING WITH THE WORK.
- 7. CONTRACTOR MUST PROTECT THE PUBLIC AND THEIR WORKERS AT ALL TIMES WITH FENCING, BARRICADES, ENCLOSURES, ETC., TO THE BEST PRACTICES PER MIOSHA GUIDELINES.
- 8. DAMAGE TO ALL EXISTING CONDITIONS TO REMAIN IN PLACE WILL BE REPLACED AT CONTRACTOR'S EXPENSE.
- 9. THE CONTRACTOR SHALL VISIT THE SITE TO VERIFY THE SIZE AND QUANTITY OF ITEMS TO BE REMOVED PRIOR TO BID.
- 10. THE CONTRACTOR SHALL ABIDE BY ALL THE REQUIREMENTS OF CLINTON COUNTY REGARDING CONSTRUCTION WITHIN OR ADJACENT TO THEIR RIGHT-OF-WAY. A COUNTY PERMIT IS REQUIRED FOR ALL CONSTRUCTION WITHIN THE COUNTY RIGHT-OF-WAY. IT IS THE CONTRACTOR'S RESPONSIBILITY TO SECURE AND PAY FOR ALL PERMITS AND BONDS PRIOR TO CONSTRUCTION, OR ENSURE THAT ALL REQUIRED PERMITS AND BONDS HAVE BEEN OBTAINED PRIOR TO CONSTRUCTION.
- 11. 11. THE CONTRACTOR MUST SUBMIT SESC APPLICATION TO CLINTON COUNTY AND SECURE PERMIT AS WELL AS TAKE OTHERS MEASURES NECESSARY TO COMPLY WITH ALL REQUIRED SOIL EROSION AND SEDIMENTATION CONTROL MEASURES.
- 12. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL FURNISH MATERIAL CERTIFICATES TO THE OWNER, VERIFYING THAT ALL MATERIALS USED ON THE PROJECT ARE IN ACCORDANCE WITH THE PLANS. SHOP DRAWINGS AND/OR CATALOG CUTS SHALL BE REQUIRED FOR MAJOR MATERIAL.
- 13. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INVESTIGATING AND DETERMINING FOR HIMSELF THE EXISTING SOIL CONDITIONS. IF THE CONTRACTOR ELECTS TO TAKE SOIL BORINGS PRIOR TO CONSTRUCTION, HE SHALL SUBMIT ONE COPY TO THE OWNER.
- 14. ALL STREET AND DRIVE PAVEMENTS SHALL BE SAW CUT PRIOR TO REMOVAL. ALL CURBS AND WALKS SHALL BE REMOVED AT THE NEAREST JOINT.
- 15. MINOR TREES, BRUSH AND VEGETATION MAY NOT BE SHOWN ON PLANS. THE CONTRACTOR SHALL BE REQUIRED TO REMOVE THEM IF NECESSARY. THE CONTRACTOR SHALL BE REQUIRED TO VERIFY ALL REMOVALS PRIOR TO CONDUCTING THE WORK.
- 16. COMPACTED GRANULAR MATERIAL MDOT CLASS II BACKFILL IS TO BE USED AT ALL ROAD CROSSINGS AND DRIVEWAYS. ALL SAND BACKFILL SHALL BE MECHANICALLY COMPACTED IN 1 FOOT LIFTS TO 95 PERCENT OF MAXIMUM UNIT WEIGHT. THOSE PORTIONS OF DRIVEWAYS DISTURBED DURING CONSTRUCTION SHALL BE RESTORED WITH LIKE MATERIAL TO THE SAME THICKNESS AS THE EXISTING PAVEMENT. ALL PAVEMENT SHALL BE REMOVED TO A SAWED STRAIGHT JOINT.
- 17. CONTRACTOR IS RESPONSIBLE FOR VEHICULAR AND PEDESTRIAN MAINTENANCE OF TRAFFIC.
- 18. BARRIER-FREE PARKING AND ACCESSIBLE ROUTES MUST COMPLY WITH THE AMERICANS WITH DISABILITIES ACT, INCLUDING BUT NOT LIMITED TO THE FOLLOWING: 1. 2% MAXIMUM CROSS-SLOPE ON ALL ACCESSIBLE ROUTES. 2. 2% MAXIMUM SLOPE IN ANY DIRECTION IN BARRIER-FREE PARKING AND ACCESS AISLES. 3. 5% MAXIMUM LONGITUDINAL SLOPE ON ACCESSIBLE ROUTES (EXCEPT WHERE RAMPS AND HANDRAILS ARE PROVIDED). 4. NO CHANGES IN LEVEL GREATER THAN ½" ALONG ACCESSIBLE ROUTE, RAMPS, OR LANDINGS.

REV# DATE DESCRIPTION E

500 Griswold Avenue, Suite 2500 Detroit, MI 48226 313.961.3650 www.wadetrim.com





asy Forest 2.0 Playground Improplayers Installation and Sitev


ISSUED FOR: DATE: BY:
MDNR Review 8/19/24 CD
90% Review 12/20/24 CD
Bid 01/16/25 CD

OB NO. CSJ200101D

G-2.0







REV# DATE DESCRIPTION

500 Griswold Aven.
Detroit, MI 48226
313.961.3650
www.wadetrim.com

ntasy Forest 2.0 Playground Improveme Playground Installation and Sitework

ISSUED FOR: DATE: BY:
MDNR Review 8/19/24 CD
90% Review 12/20/24 CD
Bid 01/16/25 CD

JOB NO. CSJ200101D

C-2.7

- ALL EROSION CONTROL MEASURES STATED ON THE SOIL EROSION CONTROL PLAN AND IN THE SWPPP SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK, OR FINAL STABILIZATION OF THE SITE. CONTRACTOR SHALL INCLUDE IN HIS BID, MAINTENANCE OF THE SOIL EROSION CONTROL DEVICES DURING THE ENTIRE PROJECT PERIOD.
- 2. EROSION CONTROL DEVICES DAMAGED BY OTHERS WILL BE REPAIRED BY OTHERS.
- REFER TO MAINTENANCE REQUIREMENTS ASSOCIATED WITH EACH BMP DETAIL AND THE

SEQUENCE OF CONSTRUCTION IN THE CONTRACT DOCUMENTS.


- 4. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON IN ACCORDANCE WITH THE CONTRACT DOCUMENTS OR THE APPLICABLE PERMIT, WHICHEVER IS MORE STRINGENT, AND REPAIRED AT NO ADDITIONAL COST TO THE OWNER IN ACCORDANCE WITH THE FOLLOWING:
  - 4.1. INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED OR REPLACED IF THEY SHOW SIGNS OF UNDERMINING OR DETERIORATION.
  - 4.2. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED, WATERED, AND RESEEDED AS NEEDED.
  - 4.3. SILT FENCES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES WHEN IT REACHES ONE-HALF THE HEIGHT OF THE SILT FENCE.
  - 4.4. CONSTRUCTION EXITS SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION EXITS AS CONDITIONS DEMAND.
  - 4.5. TEMPORARY PARKING AND STORAGE AREAS SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING AS CONDITIONS DEMAND.
  - 4.6. OUTLET STRUCTURES IN SEDIMENTATION BASINS SHALL BE MAINTAINED IN OPERATIONAL CONDITIONS AT ALL TIMES. SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS OR TRAPS WHEN THE DESIGN CAPACITY HAS BEEN REDUCED BY


#### SESC NOTES

- 1. CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES (BMPS) AS REQUIRED BY THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP). ADDITIONAL BMPS SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AT NO ADDITIONAL COST TO OWNER THROUGHOUT ALL PHASES OF CONSTRUCTION IF DEEMED NECESSARY AND RESULTANT FROM THE CONTRACTOR'S OPERATIONS, METHODS, OR SEQUENCE OF CONSTRUCTION.
- BMPS AND CONTROLS SHALL CONFORM TO FEDERAL, STATE, AND LOCAL REQUIREMENTS, OR MANUAL OF PRACTICE, AS APPLICABLE. CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS DIRECTED BY PERMITTING AGENCY OR OWNER.
- 3. CONTRACTOR SHALL MINIMIZE CLEARING TO THE MAXIMUM EXTENT PRACTICAL, OR AS REQUIRED BY THE GENERAL PERMIT.
- 4. ALL WASH WATER (CONCRETE TRUCKS, VEHICLE CLEANING, EQUIPMENT CLEANING, ETC.) SHALL BE DETAINED AND PROPERLY TREATED OR DISPOSED.
- 5. INSTALL SILT FENCES, DITCH SEDIMENT TRAPS, CHECK DAMS, INLET FILTERS, TEMPORARY GRAVEL CONSTRUCTION ENTRANCE/EXITS, TURBIDITY BARRIERS, EROSION CONTROL BLANKETS AND OTHER SOIL EROSION CONTROL DEVICES IN ACCORDANCE WITH THE DRAWINGS AND STORM WATER POLLUTION PREVENTION PLAN, OR AS MAY BE DICTATED BY SITE CONDITIONS IN ORDER TO MAINTAIN THE INTENT OF THE SPECIFICATIONS AND PERMITS.
- 6. DEFICIENCIES OR CHANGES ON THE DRAWINGS OR SWPP SHALL BE CORRECTED OR IMPLEMENTED AS SITE CONDITIONS CHANGE. CHANGES DURING CONSTRUCTION SHALL BE NOTED IN THE SWPP AND POSTED ON THE DRAWINGS.
- 7. OWNER HAS AUTHORITY TO LIMIT SURFACE AREA OF ERODIBLE EARTH MATERIAL EXPOSED BY CLEARING AND GRUBBING, EXCAVATION, BORROW AND EMBANKMENT OPERATIONS AND TO DIRECT CONTRACTOR TO PROVIDE IMMEDIATE PERMANENT OR TEMPORARY POLLUTION CONTROL
- REMOVE TEMPORARY CONTROL DEVICES AFTER PERMANENT MEASURE ARE ESTABLISHED. REMOVE AND REPLACE TEMPORARY CONTROL DEVICES IF THEY BECOME INEFFECTIVE AT NO ADDITIONAL COST TO OWNER.
- CONTRACTOR SHALL INCORPORATE PERMANENT FROSION CONTROL FEATURES PAVING PERMANENT SLOPE STABILIZATION, AND VEGETATION INTO PROJECT AT EARLIEST PRACTICAL TIME TO MINIMIZE NEED FOR TEMPORARY CONTROLS.
- 10. CONTRACTOR SHALL PERMANENTLY SEED AND MULCH CUT SLOPES AS EXCAVATION PROCEEDS TO EXTENT CONSIDERED DESIRABLE AND PRACTICAL.
- 11. CONTRACTOR SHALL PLACE ALL SOIL EROSION & SEDIMENTATION CONTROL MEASURES AS SHOWN IN THE PLANS OR AS DIRECTED BY THE ENGINEER IN ACCORDANCE WITH THE
- 12. CONSTRUCTION OPERATIONS SHALL BE SCHEDULED AND PERFORMED SO THAT PREVENTATIVE EROSION CONTROL MEASURES ARE IN PLACE PRIOR TO EXCAVATION AND TEMPORARY STABILIZATION MEASURES ARE IN PLACE IMMEDIATELY FOLLOWING BACK FILLING AND/OR
- 13. SPECIAL PRECAUTIONS WILL BE TAKEN IN THE USE OF CONSTRUCTION EQUIPMENT TO PREVENT SITUATIONS THAT PROMOTE EROSION.
- 14. THE CONTRACTOR SHALL LIMIT THE USE OF HEAVY EQUIPMENT AND OTHER CONSTRUCTION EQUIPMENT ON THE UNPROTECTED SUBGRADE.
- 15 CLEANUP WILL BE DONE IN A MANNER TO INSURE THAT EROSION CONTROL MEASURES ARE
- 16. THE PROJECT WILL CONTINUALLY BE INSPECTED FOR SOIL EROSION AND SEDIMENTATION CONTROL COMPLIANCE. ALL DEFICIENCIES WILL BE CORRECTED BY THE CONTRACTOR WITHIN 24
- 17. TEMPORARY EROSION CONTROL MEASURES SHALL BE COMPLETELY REMOVED BY THE CONTRACTOR UPON ESTABLISHMENT OF PERMANENT CONTROL MEASURES AND AS DIRECTED BY LOCAL APPROVING AGENCY.
- 18. CONSTRUCTION WILL NOT DISTURB MORE THAN 5 ACRES, THUS A NPDES STORM WATER DISCHARGE PERMIT WILL NOT BE REQUIRED.
- 19. ALL ROADS WITHIN THE INFLUENCE OF THE PROJECT MUST REMAIN CLEAN AT ALL TIMES. CONTRACTOR SHALL SWEEP STREETS AS DIRECTED BY LOCAL MUNICIPALITY HAVING JURISDICTION OVER THE ROADWAY (I.E. TOWNSHIP, CITY, COUNTY, STATE, ETC).
- 21. BEST MANAGEMENT PRACTICES FOR SOIL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE USED ON THIS PROJECT AS SHOWN ON THE PLANS AND AS DEFINED BY THE
- 22. THE CONTRACTOR SHALL SUBMIT A DETAILED SOIL EROSION AND SEDIMENTATION CONTROL PLAN AND OBTAIN AN ACT 451 PART 91, SOIL EROSION AND SEDIMENTATION CONTROL PERMIT, COPY TO BE PROVIDED TO THE ENGINEER. THE CONTRACTOR IS RESPONSIBLE FOR THE PAYMENT OF APPLICATION FEES, REVIEW FEES, INSPECTION FEES, BONDS, ETC. NO EARTH CHANGES OR EXCAVATION SHALL BE STARTED PRIOR TO THE ISSUANCE OF THIS PERMIT.
- 23. TEMPORARY SEEDING SHALL BE MAINTAINED DURING THE PERIOD OF CONSTRUCTION UNTIL THE CONTRACT HAS BEEN COMPLETED AND ACCEPTED.
- 24. ALL DENSE GRADED AGGREGATE SHALL BE MDOT 6A OR AASHTO #57.

#### **SESC SPECIFICATIONS**

- 1. SILT FENCE SHALL BE POLYPROPYLENE GEOTEXTILE FABRIC, RESISTANT TO COMMON SOIL CHEMICALS, MILDEW, AND INSECTS; NON-BIODEGRADABLE; IN LONGEST LENGTHS POSSIBLE; MEETING THE FOLLOWING REQUIREMENTS:
- 1.1. AVERAGE OPENING SIZE: 30 U.S. STD. SIEVE, MAXIMUM; ASTM D4751.
- PERMITTIVITY: 0.05 SEC<sup>-1</sup>, MINIMUM; ASTM D4491. ULTRAVIOLET RESISTANCE: RETAINING AT LEAST 70% OF TENSILE STRENGTH; ASTM D4355 AFTER 500 HOURS EXPOSURE.
- 1.4. TENSILE STRENGTH: 100 LB-F (445 N) MINIMUM, IN CROSS-MACHINE DIRECTION; 124 LB-F (551 N) MINIMUM IN MACHINE DIRECTION; ASTM D4632.
- 1.5. ELONGATION: 15 TO 30%; ASTM D4632 1.6. TEAR STRENGTH: 55 LB-F (244 N) MINIMUM; ASTM D4533.
- 2. UV-STABILIZED, NON-WOVEN GEOTEXTILE BAG TO FILTER SEDIMENT FROM WATER PRIOR TO DISCHARGING. GEOTEXTILE FABRIC SHALL MEET THE FOLLOWING MINIMUM AVERAGE ROLL
- TENSILE STRENGTH: 180 LB-F (200 N) MINIMUM; ASTM D4632
- 2.2. ELONGATION: 50 PERCENT MINIMUM; ASTM D4632 2.3. CBR PUNCTURE STRENGTH: 300 LB-F MINIMUM; ASTM D6241
- 2.4. TRAPEZOIDAL TEAR: 70 LB-F MINIMUM; ASTM D4533 2.5. FLOW RATE: 80 GAL/MIN/SF. MINIMUM; ASTM D4491
- 2.6. PERMITTIVITY: 1.4 SEC <sup>-1</sup> MINIMUM; ASTM D4491 APPARENT OPENING SIZE: 80 U.S. STD. SIEVE MAXIMUM; ASTM D4751 2.8. UV-STABILITY: 70% RETAINED STRENGTH; ASTM D4355 AFTER 500 HOURS.
- 3. EROSION CONTROL BLANKETS SHALL BE MACHINE PRODUCED BLANKET WITH A CONSISTENT THICKNESS OF EVENLY DISTRIBUTED STRAW OR COCONUT FIBER AS SPECIFIED. UNLESS OTHERWISE SPECIFIED ON THE PLANS, THE EROSION CONTROL BLANKET SHALL HAVE THE FOLLOWING MINIMUM PROPERTIES:
- 3.1. DOUBLE NET 100% STRAW BLANKET.
- 3.2. TOP AND BOTTOM PHOTODEGRADABLE POLYPROPYLENE NETTING, 1.64 LBS./1,000 SFT. APPROXIMATE WEIGHT.
- 3.3. 100% AGRICULTURAL STRAW 0.5 LBS/SY.
- 3.4. STITCH SPACING: 1.5 INCHES (40 MM) ON CENTERS. PEGS SHALL BE 6-INCH (150 MM) LONG, HARDWOOD PEGS.
- 4. FILTER FABRIC SHALL BE CONSTRUCTED OF 100% CONTINUOUS POLYESTER NEEDLE-PUNCHED NON-WOVEN ENGINEERING FABRIC. FILTER FABRIC SHALL BE FABRICATED TO PROVIDE A DIRECT FIT WITH THE DRAINAGE STRUCTURE COVER. FILTER FABRIC SHALL HAVE THE FOLLOWING MINIMUM PHYSICAL PROPERTIES.
- 4.1. TENSILE STRENGTH: 80 LB-F MINIMUM; ASTM D4632
- 4.2. ELONGATION: 50 PERCENT MINIMUM; ASTM D4632 4.3. CBR PUNCTURE STRENGTH: 300 LB-F MINIMUM; ASTM D6241
- 4.4. TRAPEZOIDAL TEAR: 70 LB-F MINIMUM; ASTM D4533
- 4.5. FLOW RATE: 80 GAL/MIN/SF. MINIMUM; ASTM D4491
  4.6. PERMITTIVITY: 1.4 SEC -1 MINIMUM; ASTM D4491
  4.7. APPARENT OPENING SIZE: 100 U.S. STD. SIEVE MAXIMUM; ASTM D4751 4.8. UV-STABILITY: 70% RETAINED STRENGTH; ASTM D4355 AFTER 500 HOURS.







<u>PLAN VIEW</u>

NOTE: PAVED/CONC AND GRAVEL PAVEMENT AREA APPLICATION

## CATCH BASIN PROTECTION (TYPE II)






PLAN VIEW

NOTE: DIRT AREA APPLICATION

CATCH BASIN PROTECTION DETAIL (TYPE I)

NOT TO SCALE



POST SPACING: 6-FOOT MAX

UNTREATED STORM FLOWS.

FABRIC: 36 INCHES IN WIDTH, MUST MEET ASTM D6461, 4 FT MINIMUM OVERLAP AT JOINTS (ENDS).

STONE: IF SILT FENCE IS DESIGNED AND UTILIZED AS A DIVERSION, PLACE OPEN GRADED AGGREGATE WASHED STONE 12 INCHES DEEP AT SILT FENCE AS SHOWN. CURL EACH END OF THE SILT FENCE UPHILL IN A "J" PATTERN TO PREVENT RELEASE OF

> SILT FENCE DETAIL NOT TO SCALE

> > 1.5 x CROWN DRIP LINE OR OTHER LIMIT OF TREE PROTECTION AREA.


SEE TREE PRESERVATION PLAN FOR FENCE ALIGNMENT.

SECTION A

<u>PLAN</u>

TREE PROTECTION FENCE DETAIL

NOT TO SCALE



## CONSTRUCTION

- 1. CLEAR THE ENTRANCE AND EXIT AREA OF ALL VEGETATION, ROOTS, AND OTHER OBTRUSIVE MATERIAL AND GRADE TO HAVE A SMOOTH, EVEN SURFACE
- PLACE THE GRAVEL TO THE SPECIFIC GRADE AND DIMENSIONS SHOWN ON THE PLANS, AND SMOOTH IT PROVIDE POSITIVE DRAINAGE TO CARRY WATER TO A SEDIMENT TRAP OR OTHER SUITABLE OUTLET.
- 4. USE GEOTEXTILE FILTER FABRIC PER 01 57 13 TO IMPROVE STABILITY OF THE FOUNDATION IN LOCATIONS SUBJECT TO SEEPAGE OR HIGH WATER TABLE.

#### MAINTENANCE

2" x 6' STEEL OR WOODEN

SUPPORT POSTS EVERY 8'.

2' INTO THE GROUND

INSTALL POSTS A MINIMUM OF

-4' HIGH FENCE AS SPECIFIED

THROUGHOUT THE CONSTRUCTION

PROTECTION FENCE TO BE MAINTAINED

AND PLACED AT THE TREE

DRIPLINE

PERIOD

MAINTAIN THE CONSTRUCTION ENTRANCE IN A CONDITION TO PREVENT MUD OR SEDIMENT FROM LEAVING THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH 2-INCH STONE. AFTER EACH RAINFALL, INSPECT STRUCTURE USED TO TRAP SEDIMENT AND CLEAN IT OUT AS NECESSARY. IMMEDIATELY REMOVE MATERIALS SPILLED, WASHED, OR TRACKED ONTO PUBLIC

SEE SOIL EROSION CONTROL PLAN FOR ACTUAL OVERALL DIMENSION OF EACH CONSTRUCTION ACCESS DRIVE. MINIMUM SIZES SHOWN IN THIS DETAIL APPLY WHEN NO DIMENSIONS ARE SHOWN ON PLAN.

TEMPORARY GRAVEL CONSTRUCTION ENTRANCE



TREE PROTECTION FENCE: HIGH

DENSITY POLYETHYLENE FENCING

3.5" x 1.5" OPENINGS.

-2" x 6' STEEL OR WOODEN

SUPPORT POSTS EVERY 8'.

5" THICK LAYER OF MULCH

- MAINTAIN EXISTING GRADE

INDICATED ON PLANS

FENCE UNLESS OTHERWISE

INSTALL POSTS A MINIMUM OF 2'

COLOR: ORANGE

INTO THE GROUND

- 1. NO PRUNING SHALL BE PERFORMED EXCEPT BY APPROVED
- 2. NO EQUIPMENT SHALL OPERATE INSIDE THE PROTECTIVE FENCING INCLUDING DURING FENCE INSTALLATION AND REMOVAL.
- 3. APPROVED TREE PROTECTION SHALL BE ERECTED PRIOR TO THE START OF CONSTRUCTION ACTIVITIES, AND SHALL REMAIN IN PLACE UNTIL CONSTRUCTION IS COMPLETE.
- NO PERSON MAY CONDUCT ANY ACTIVITY WITHIN THE DRIP LINE OF ANY DESIGNATED TREE TO REMAIN, INCLUDING, BUT NOT LIMITED TO, PLACING SOLVENTS, BUILDING MATERIALS, CONSTRUCTION EQUIPMENT, OR SOIL DEPOSITS WITHIN THE DRIP
- GRADE CHANGES MAY NOT OCCUR WITHIN THE DRIP LINE OF PROTECTED TREES.
- 6. DURING CONSTRUCTION, NO PERSON SHALL ATTACH ANY DEVICE OR WIRE TO ANY REMAINING TREE.
- 7. ALL UTILITY SERVICE REQUESTS MUST INCLUDE NOTIFICATION TO THE INSTALLER THAT PROTECTED TREES MUST BE AVOIDED. ALL TRENCHING SHALL OCCUR OUTSIDE OF THE PROTECTIVE FENCING.

8. SWALES SHALL BE ROUTED TO AVOID THE AREA WITHIN THE DRIP

LINES OF PROTECTED TREES. TREES LOCATED ON ADJACENT PROPERTIES THAT MAY BE WITHIN THE TREE PROTECTION 9. AFFECTED BY CONSTRUCTION ACTIVITIES MUST BE PROTECTED. 10. ROOT ZONES OF PROTECTED TREES SHOULD BE WELL MARKED

WITH BRIGHT COLORS AND SURROUNDED WITH RIGIDLY STAKED

- 11. THE PARKING OF IDLE AND RUNNING EQUIPMENT SHALL BE PROHIBITED UNDER THE DRIP LINE OF PROTECTED TREES.
- 12. THE STRIPPING OF TOPSOIL FROM AROUND PROTECTED TREES SHALL BE PROHIBITED.
- 13. TREES TO BE REMOVED SHALL BE FELL AWAY FROM TREES TO
- 14. GRUBBING OF UNDERSTORY VEGETATION IN CONSTRUCTION AREAS SHOULD BE CLEARED BY CUTTING VEGETATION AT GROUND LEVEL WITH A CHAIN SAW OR MINIMALLY WITH A HYDRO-AXE.
- 15. THE LANDSCAPE ARCHITECT SHALL BE NOTIFIED IMMEDIATELY IF ANY PROTECTED TREE IS DAMAGED OR REMOVED.

NOTE: GENERAL CONTRACTOR TO COMPLETE TABLE WITH THEIR SPECIFIC PROJECT SCHEDULE JAN FEB MAR APR MAY JUN JUL AUG SEP OCT NOV DEC JAN FEB CONSTRUCTION SEQUENCE TEMPORARY CONSTRUCTION EXITS TEMPORARY CONTROL MEASURES SEDIMENT CONTROL BASINS STRIP & STOCKPILE TOPSOIL ROUGH GRADE STORM FACILITIES SITE CONSTRUCTION PERMANENT CONTROL STRUCTURES FOUNDATION / BUILDING CONSTRUCTION FINISH GRADING

LANDSCAPING/SEED/FINAL STABILIZATION

SOIL EROSION/SEDIMENTATION CONTROL OPERATION TIME SCHEDULE

CSJ200101D

MDNR Review 8/19/24


90% Review 12/20/24


01/16/25

ರ

0

αД





Improvemed Sitework of St. Johns
Playground Installation and tasy Forest Playground SITE PLAN

ISSUED FOR: DATE: BY: MDNR Review 8/19/24 CD 90% Review 12/20/24 CD eview 8/19/24 CD iew 12/20/24 CD 01/16/25 CD

CSJ200101D

C - 3.1




Fantasy Forest 2.0 Playground Improvements
Playground Installation and Sitework

SITE PLAN - POURED IN PLACE ENLARGEMENT

CSJ200101D

C-3.2






City of St. Johns antasy Forest 2.0 Playground Improvements Playground Installation and Sitework

| ISSUED FOR: DATE: BY: | MDNR Review 8/19/24 CD | 90% Review 12/20/24 CD | Bid | 01/16/25 CD | 0


CSJ200101D

C - 4.1



4" CONCRETE SIDEWALK DETAIL NOT TO SCALE


-INTERNATIONAL SYMBOL OF ACCESSIBILITY MEETING BARRIER



NOTE:
1. CONTRACTOR CAN USE EXISTING CRUSHED SITE CONCRETE/ASPHALT AS AGGREGATE BASE MATERIAL (CONTRACTOR SHALL INCREASE BASE THICKNESS BY 25%) 2. CONTRACTOR WILL COMPACT SUBGRADE AND PLACE AND COMPACT AGGREGATE BASE. HMA PAVEMENT WILL BE INSTALLED BY OTHERS AND COORDINATED WITH OWNER.

STANDARD HMA PAVEMENT **DETAIL** 

NOT TO SCALE



TRENCH WIDTHS

MAX WIDTH OF TRENCH 12" ABOVE TOP OF PIPE

6" THRU 12" PIPE - 30" WIDE

15" THRU 36" PIPE - 0.D. + 16"

TYPICAL TRENCH DETAIL NOT TO SCALE

-DUAL WALL HDPE STORM

-PROPOSED LANDSCAPE, PER

-2-4" EGG ROCK OR


-2-4" EGG ROCK OR

COBBLES

FINISH GRADE

COBBLES.

SEWER OUTLET




UNDERDRAIN DETAIL

NOT TO SCALE

PAVEMENT OR CONCRETE

SECTION


6" STANDARD **CURB & GUTTER DETAIL** 




6" CONCRETE STRAIGHT CURB DETAIL NOT TO SCALE




**SURFACING TRANSITION** 





POURED PROTECTIVE SURFACING W/CONCRETE EDGE



COURSE AND TOP CAP INSTALLATIONS.

10% ———

PROTECTIVE SURFACING EDGE WITH MULCH

UNDISTURBED SUBGRADE

PLAN

DUAL WALL HDPE STORM-

SEWER OUTLET

12" MIN ENGINEERED WOOD FIBER FINISHED DEPTH AFTER COMPACTION GEOTEXTILE FABRIC TYP. - POURED PROTECTIVE EPDM SURFACING TOP CAP DEPTH PER MANUF. SPEC. BASED ON FALL HEIGHTS SHOWN ON C-3.2 (1/2" MIN. THICKNESS) BASE COURSE PER MANUF. SPEC. SLOPE 2%-1/4" OVER 10' - DEPTH VARIES - 4" MIN. AGGREGATE BASE , MDOT 21AA UNDISTURBED SUBGRADE

EWF PLAY BORDER TO PROTECTIVE EPDM

-BOTTOM OF HMA OR

-OPEN GRADED

AROUND AGGREGATE

AT A MIN. OF 1.0%

NOTES

AGGREGATE, SEE

GEOTEXTILE FABRIC WRAP

PIPE W GEOTEXTILE FABRIC

WRAP, SLOPE UNDER DRAIN

CONCRETE AGGREGATE BASE

6" PERFORATED DUAL—WALL H.D.PE.


Sity of St. Johns 2.0 Playground Installation and SITE DETAILS y Forest asy Pla


500 Griswold Aven Detroit, MI 48226 313.961.3650


SUED FOR: DATE: MDNR Review 0 25 20 24 90% Review 0 25 20 24

CSJ200101D

C - 5.0







 MOST DEPENDABLE FOUNTAINS MODEL
 10145 DRINKING FOUNTAIN WITH PET FOUNTAIN. SURFACE MOUNT WITH 2" OPEN HUB DRAIN.

THE PRODUCT MANUFACTURER TO BE CONSIDERED ACCURATE.

5. CONTRACTOR'S NOTE: FOR PRODUCT AND COMPANY INFORMATION VISIT www.CADdetails.com/info AND ENTER REFERENCE NUMBER 3354-17.52

MOST DEPENDABLE FOUNTAINS, INC

PUSH BUTTON FOR ¬

ADA ARM

BOLT IS CENTERED -

OPTIONAL TEMPLATE ~

BOLT IS CENTERED -UNDER "ADA ARM"

2. NOTE TO ARCHITECT, SCALE DRAWING IN AUTOCAD MODEL SPACE.

MODEL 10145 SM SHOWN W/ OPTIONAL PET FOUNTAIN

PROTECTED BY COPYRIGHT ©2019 CADDETAILS.COM LTD.

1. INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

IF TYING INTO A SANITARY SEWER, A P-TRAP WIL

MODEL 10145 DRINKING FOUNTAIN NO SCALE

MOST DEPENDABLE FOUNTAINS, INC.

5705 COMMANDER DR. P.O. BOX 587 ARLINGTON, TN 38002-0587 PHONE: (901) 867-0039


www.mostdependable.com

--- PET FOUNTAIN ON


- REMOVE DOG BOWL

OR 4" OPEN HUB DRAIN
FRONT VIEW
6 5/8" SLEEVE

TOP VIEW



WASAU TILE LITTER BIN MF3302 NOT TO SCALE



1. FENCE TO BE 3' TALL WITH STANDARD POST OPTION.

ORNAMENTAL FENCE DETAIL


City of St. Johns
2.0 Playground Improvem
d Installation and Sitework
SITE DETAILS antasy Forest Playground

| ISSUED FOR: DATE: BY: | MDNR Review 8/19/24 CD | 90% Review 12/20/24 CD | Bid | 01/16/25 CD | O

CSJ200101D

C - 5.1





ECO-TURF LOW MAINTENANCE FESCUE

REV# DATE DESCRIPTION
DATE
DESCRIPTION

CSJ200101D

L-1.0


**GROUNDCOVER PLANTING DETAIL** NOT TO SCALE

LANDSCAPE BOULDER PLACEMENT DETAIL NOT TO SCALE

→ BOULDER


FINISH GRADE

UNDISTURBED SOIL



- 1. FOR CONTAINER-GROWN TREES, USE FINGERS OR SMALL HAND TOOLS TO PULL THE ROOTS OUT OF THE OUTER LAYER OF POTTING SOIL; THEN CUT OR PULL APART ANY ROOTS CIRCLING THE PERIMETER OR THE CONTAINER.
- 2. AFTER DIGGING HOLE, FILL WITH WATER TO CONFIRM THAT WATER DRAINS OUT OF THE SOIL. IF HOLE DOES NOT PERC, DO NOT PLANT TREE. NOTIFY LANDSCAPE ARCHITECT FOR DIRECTION.
- 3. THOROUGHLY SOAK THE TREE ROOT BALL AND ADJACENT PREPARED SOIL IMMEDIATELY AFTER PLANTING.
- 4. THE PLANTING PROCESS IS SIMILAR FOR DECIDUOUS AND EVERGREEN TREES.
- 5. PURCHASE TREE WITH ONE CENTRAL LEADER. DO NOT PRUNE TREE AT PLANTING EXCEPT AS DIRECTED BY LANDSCAPE ARCHITECT.
- 6. SET TREE PLUMB WITH VERTICAL TRUNK.
- 7. STAKE TREES ONLY UPON THE APPROVAL OF THE LANDSCAPE ARCHITECT.
- 8. WRAP TREES ONLY UPON THE APPROVAL OF THE LANDSCAPE ARCHITECT.

#### TREE PLANTING DETAIL NOT TO SCALE



SHRUB PLANTING DETAIL

NOT TO SCALE

#### **PLANTING NOTES**

1. LANDSCAPE PLANTING DETAILS ARE PROVIDED FOR REFERENCE ONLY. INSTALLATION OF INDIVIDUAL PLANTS WILL BE DONE BY CITY STAFF AND VOLUNTEERS AT PUBLIC PLANTING DAY TO BE COORDINATED DURING SUMMER 2025.

FIGURE EIGHT LOOP - PLASTIC FLAGGING AROUND TREE TAPE OR OTHER VISUAL MARKER ON WEBBED STRAP EACH STRAP, TYP. MATERIAL. SEE NOTE 3 OPTIONAL: METAL DRIVE ANCHORS 30" LONG WOODEN **INSTALLED PER** MANUFACTURER'S DIRECTIONS UNDISTURBED ➤ BACKFILLED SOIL FOR TREE PLANTING

NOTES:

1. REMOVE ALL STAKING AS SOON AS THE TREE HAS GROWN SUFFICIENT ROOTS TO OVERCOME THE PROBLEM THAT REQUIRED THE TREE TO BE STAKED. STAKES SHALL BE REMOVED NO LATER THAN THE END OF THE FIRST GROWING SEASON AFTER PLANTING.

- 2. TIGHTEN WEBBED STRAP MATERIAL ONLY ENOUGH TO KEEP FROM SLIPPING. ALLOW FOR SOME TRUNK MOVEMENT. INSTALL THREE STRAPS PER TREE, SPACED EVENLY AROUND THE
- TRUNK. INSTALL AS LOW ON TRUNK AS POSSIBLE. 3. WEBBED STRAP TO BE ARBORTIE OR APPROVED EQUAL
- 4. TREES NORMALLY DO NOT NEED TO BE STAKED AND STAKING CAN BE HARMFUL TO THE TREE. STAKING SHOULD BE DONE ONLY WITH THE APPROVAL OF THE LANDSCAPE ARCHITECT IF IT IS EXPECTED THAT THE TREE WILL NOT BE ABLE TO SUPPORT ITSELF. THE FOLLOWING ARE REASONS WHY TREES DO NOT REMAIN STRAIGHT. 4.1. TREES WITH POOR-QUALITY ROOT BALLS OR ROOT BALLS THAT HAVE BEEN CRACKED OR
- DAMAGED . REJECT RATHER THAN STAKE. 4.2. TREES THAT HAVE GROWN TOO CLOSE TOGETHER IN THE NURSERY, RESULTING IN
- WEAK TRUNKS. REJECT RATHER THAN STAKE. 4.3. PLANTING PROCEDURES THAT DO NOT ADEQUATELY TAMP SOILS ARE THE ROOT BALL.
- CORRECT THE PLANTING PROCEDURE. 4.4. ROOT BALLS PLACED ON VERY SOFT SOIL. TAMP SOILS UNDER ROOT BALL PRIOR TO
- 4.5. ROOT BALLS WITH VERY SANDY SOIL OR VERY WET SOIL. STAKING ADVISABLE. 4.6. TREES LOCATED IN A PLACE OF EXTREMELY WINDY CONDITIONS. STAKING ADVISABLE.

TREE STAKING DETAIL

NOT TO SCALE



zem ork Improve | Sitewo of St. Johns
Playground Istallation and

MDNR Review 8/19/24 CD 90% Review 12/20/24 CD Bid 01/16/25 CD

CSJ200101D

L-2.0

#### Michigan Wildflower Farm -Eco-Turf Low Maintenance Fescue Mix

Seeding Rate - 7 lbs./1000 s.f. or 300 lbs./acre

\$5.25/lb.		
Coverage Area	Weight	Cost
1/4 acre	75 lbs.	\$393.75
1/2 acre	150 lbs	\$787.50
3/4 acre	225 lbs.	\$1181.25
1 acre	300 lbs.	\$1575,00

Due to fescue shortages, the EcoTurf Mix seeds are costed with ProNitro TM, which includes limestone with polymer, micronutrients, kelp and beneficial mycorrhizae. This added coating assures stronger germination and faster establishment.

This drought-tolerant mix provides a turf which can establish in deep shade, full sun and even the most neglected areas. Consider seeding this mix in your landscape to cut back on your lawn maintenance time and

Our Eco-Turf seed mix consists of five slow growing fescues. These are not native Michigan genotype species, but are offered as an alternative to traditional turf grass mixes. Because these species are slowing growing. required, mowing can take place but with less frequency. We moved our Eco-Turf three times this year and mowed our traditional lawn area seven times! Some of our customers choose not to mow the Eco-Turf at all as they enjoy the soft and fine texture appearance.

The five fescues in Eco-Turf make this mix suitable for sunny/pertial shade. loam/sand/gravel and well-drained clay soils. Also, once established. carefree Eco-Turf is durable in high traffic areas. The optimal time for seeding this mix is mid-to-late August through September, although seeding in mid-to-late March through May is also possible.

Prior to seeding, the planting area needs to be as weed free as possible and we recommend preparation steps laid out in our 'Ten Steps to a Successful Wildflower Planting," Watering the site initially can accelerate establishment. We have not irrigated our Eco-Turf lawn ever. Fertilizing is not needed, however, if broadleaf weeds become a problem, a broadleaf erbicide can be used.


#### Michigan Wildflower Farm -Short Woodland Mix

40% Forbs, 60% Grasses

5 oz/1000 s.f. or 10 lbs/acre \$14.50/oz. or \$232/lb.

Our seeds are available in any amount, no matter how small or large your project.

Coverage Area	Weight	Cost
1/4 acre	2.5 lbs.	\$580,00
1/2 acre	5 lbs.	\$1,60.00
3/4 acre	7.5 lbs.	\$1,740.00
1 acre	10 lbs.	\$2,232.00



#### Short Woodland Mix - Forbs

#### Short Woodland Mix - Grasses

Scientific Name	Common Name	Scientific Name	Common Name		
Achilles millefolium	Yarrow	Boutelous curtipenduls	Side-oats Grama		
Allium cernuum	Nodding Wild Onion	Elymus hystrix	Bottlebrush Grass		
Anemone virginiana	Tall Thimbleweed	Koeleria macrantha	June Grass		
Aquilegia cenedensis	Wild Columbine	Schizachyrium scoparius	Little Bluestem		
Asciepias tuberosa	Butterfly Weed				
Echinacea purpurea	Purple Conefiower	A note about sover o			
Monarda fistulosa	Wild Bergamot	A note about cover crop  If you are seeding on bare soil or slope, we recommend including temporary cover crop at a rate of 15 lbs. per acre, \$3 per lb.			
Pensternon digitalis	Foxglove Beard-tongue				
Penstemon hirsutus	Hairy Beard-tongue				
Rudbeckis hirta	Black-eyed Susan	The second secon	est finding cover crop locally as they		
Rudbeckia triloba	Three-lobed Coneflower	commonly available and are heavy cost with us.	adding substantially to your shippin		
Symphyotrichum laeve	Smooth Aster				
Symphyotrichum oolentangiensis	Prairie Heart-leaved Aster				
Symphyotrichum pilasum	Hairy Aster				
Thalictrum diolcum	Early Meadow Rue				
Zizee aurea	Golden Alexander				

## Michigan Wildflower Farm -Raingarden Mix

40% Forbs, 60% Grasses/Sedge/Rush 3 oz./1000 s.f. or 6 lbs./acre

\$16.50/az. or \$264/lb. Our seeds are available in any amount, no matter how small or large your project.

Coverage Area	Weight	Cost
1/4 acre	15 lbs.	\$396.00
1/2 acre	3 lbs.	\$792.00
3/4 acre	4.5 lbs.	\$1,188.00
1 acre	6 lbs.	\$1,584.00

# Mix Ratio Forbs 40%

#### Raingarden Mix - Forbs

Verbene hastata

Vemonia missurica

Scientific Name	Common Name	Scientific Name		
Ariemone canadensis	Canada Anemone	Carex spp.		
Angelica atropurpurea	Angelica	Elymus virginicus		
Asclepias incarnata	Swamp Milkweed	Scirpus spp.		
Eupatorium maculatum	Jae-Pye Weed	Sperganium eury		
Eupatorium perfoliatum	Boneset			
Helenium autumnale	Sneezeweed	A X O ROSE NO CONTRACTO		
Hibiscus mosheutos	Swamp Rose Mallow	A note abo		
fris virginica	Southern Blue Flag	If you are seeding temporary cover of		
Liatris spicata	Marsh Blazing Star			
Lobelia siphilitica	Great Blue Lobelia	If you have large a		
Rudbeckia fulgida	Sweet Black-eyed Susan	commonly availab cost with us.		
Solidago graminifolia	Grass-leaved Goldenrod			
Symphyotrichum puniceum	Swamp Aster			

Blue Vervain

Ironweed

#### Raingarden Mix - Grasses

ie.	Common Name
	Carex species
98	Virginia Wild Rye
	Scirpus species
rycarpum	Common Bur Reed
out cover ci	op
ig on bare soil or sl	ope, we recommend including a
r crop at a rate of 1	5 lbs. per acre, \$3 per lb.
acreage, we sugge	st finding cover crop locally as they are
	adding substantially to your shipping

#### LANDSCAPE NOTES

- 1. ALL PLANTS TO BE INSTALLED IN ACCORDANCE WITH AMERICAN ASSOCIATION OF NURSERYMEN LANDSCAPE STANDARDS.
- 2. CONTRACTOR SHALL PROVIDE A PLANTING MIXTURE MEETING THE FOLLOWING REQUIREMENTS. IF THE ENGINEER HAS ANY CONCERNS WITH THE QUALITY OF THE PLANTING MIXTURE, THE ENGINEER SHALL BE ALLOWED TWO WEEKS TO OBTAIN SOIL TEST TO DETERMINE SPECIFICATION COMPLIANCE. NO PLANT MATERIAL SHALL BE PLANTED PRIOR TO ENGINEER APPROVAL OF PLANTING MIXTURE. ALL PLANT MATERIAL SHALL BE MAINTAINED BY THE CONTRACTOR IN A VIGOROUS GROWING CONDITION DURING THIS TIME AT NO ADDITIONAL COST.
- 3. SPACING OF PLANT MATERIALS SHALL BE AS SHOWN ON DRAWING OR ON PLANT LIST. THE ENGINEER SHALL REVIEW THE PLACEMENT OF PLANT MATERIAL PRIOR TO AND AFTER INSTALLATION, AND RESERVES THE RIGHT TO ADJUST LAYOUT TO ACCOMMODATE SITE CONDITIONS AND DESIGN INTENT.
- 4. ALL PLANT MATERIALS SHALL CONFORM TO PLANT SCHEDULES. SIZES SHALL BE THE MINIMUM STATED ON THE PLANT LIST OR LARGER. ALL MEASUREMENTS SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE "A.A.N. STANDARDS FOR NURSERY
- 5. NO PLANT SHALL BE PUT INTO THE GROUND BEFORE ROUGH GRADING HAS BEEN FINISHED AND REVIEWED BY THE ENGINEER.
- 6. FINAL PLANT LOCATIONS SHALL BE MARKED BY CONTRACTOR THREE WORKING DAYS PRIOR TO PLANTING FOR ENGINEER REVIEW. 7. ALL PLANTED PLANTS SHALL BEAR THE SAME RELATIONSHIP TO FINISHED GRADE AS THE PLANTS ORIGINAL GRADE BEFORE
- 8. PLANT MATERIAL, ESPECIALLY EVERGREENS, TO BE PLANTED HIGHER THAN NORMAL WHEN HEAVY SOIL CONDITIONS (CLAY, ETC.)
- 9. IF FOR ANY REASON ANY BALLED AND BURLAPED PLANT MATERIALS NEED TO BE STORED ON SITE LONGER THAN A 24-HOUR PERIOD, THEIR ROOT BALLS SHALL BE PROTECTED. ALL PLANTS SHALL BE THOROUGHLY WATERED EACH DAY THEY ARE STORED ON SITE. PLANTS MAY BE STORED ON SITE FOR A MAXIMUM OF TWO (2) WEEKS, OR 14 DAYS. ANY PLANTS ALLOWED TO DRY OUT AS DETERMINED BY THE ENGINEER WILL BE REJECTED.
- 10. NO CONTAINER GROWN STOCK WILL BE ACCEPTED IF IT IS ROOT BOUND. ALL WRAPPING MATERIALS MADE OF SYNTHETIC OR PLASTICS SHALL BE COMPLETELY REMOVED AT TIME OF PLANTING.
- 11. THE CONTRACTOR SHALL FILL PLANT PIT WITH PREPARED PLANT MIX TO ½ DEPTH OF ROOT BALL OR ROOT MASS, PACK FIRMLY, PUDDLE WITH WATER; THEN FOR BALLED AND BURLAPED MATERIAL, THE BURLAP AND ALL LACING (INCLUDING WIRE BASKET IF NECESSARY) SHALL BE REMOVED FROM THE UPPER 1/3 OF ROOTBALL, THEN FINISH BACKFILLING ADDING SOLID FERTILIZER TO THE PLANT MIX, PACK FIRMLY AND WATER. A SAUCER SHALL BE PLACED AROUND EVERY PLANT AND SHALL BE APPROVED PRIOR TO PLACEMENT OF ANY MULCH.
- 12. ALL DISTURBED LAWN AREAS SHALL BE RESTORED WITH 4-INCHES OF TOPSOIL, SPREAD, FINE GRADED, AND SEEDED/SODDED AS SPECIFIED. PRIOR TO INSTALLATION OF TOPSOIL, LOOSEN SUBGRADE TO A DEPTH OF 2 INCHES. THIS WORK SHALL BE INCIDENTAL
- 13. TOPSOIL SHALL CONSIST OF FRIABLE, SHREDDED, AND SCREENED SOIL REASONABLY FREE OF GRASS, ROOTS, WEEDS, STICKS, STONES OR OTHER FOREIGN MATERIALS. THE TOPSOIL MATERIAL SHALL BE APPROVED BY THE ENGINEER PRIOR TO PLACEMENT. SOIL COMPOSITION SHOULD CONTAIN AN ORGANIC CONTENT OF 2 TO 6 PERCENT AND BE CLASSIFIED AS A LOAM OR SANDY LOAM AS SPECIFIED IN THE "GUIDE FOR U.S.D.A. SOIL TEXTURAL CLASSIFICATION".
- 14. ALL TREES AND SHRUBS ARE TO BE FERTILIZED ONCE ROOTS SYSTEM IS ESTABLISHED WITH AGRIFORM 21-GRAM FERTILIZER
- TABLETS AT RATES RECOMMENDED BY MANUFACTURER.

16. AT PLANTING TIME, ALL DEAD AND BROKEN BRANCHES SHALL BE PRUNED ON ALL DECIDUOUS TREES.

- 15. ALL PLANTS AND STAKES SHALL BE SET PLUMB UNLESS OTHERWISE SPECIFIED.
- 17. CONTRACTOR SHALL APPLY ENGINEER APPROVED PRE-EMERGENT HERBICIDE, "PREEN" OR EQUAL, TO SHRUB AND GROUND COVER PLANTING AREAS AT THE TIME OF PLANTING (IF SPRING PLANTED) OR THE FOLLOWING SPRING. CONTRACTOR SHALL ENSURE THE PLANT MATERIALS ARE RESISTANT TO THE HERBICIDES PROPERTIES. HERBICIDE SHALL BE APPLIED ACCORDING TO MANUFACTURERS SPECIFICATIONS AND IN ACCORDANCE WITH SOUND HORTICULTURAL PRACTICES.
- 18. ALL TREES, SHRUBS AND PERENNIAL GROUND COVER SHALL RECEIVE A MINIMUM DEPTH OF THREE INCHES DOUBLE SHREDDED HARDWOOD BARK MULCH. WHERE PLANT BEDS MEET PAVEMENTS, LAWN, OR STEEL EDGING CUT THE GRADE TO ALLOW FOR MULCH AND THREE-INCH DROP FROM ADJOINING FINISH GRADE.
- 19. ALL PLANT BEDS SHALL BE EXCAVATED TO A MINIMUM DEPTH OF 8-INCHES AND BACKFILLED WITH SPECIFIED PLANT MIX AS PER PLANTING BED DETAILS. BEDS SHALL BE EDGED WITH METAL EDGING AROUND PERIMETER. ALL EDGING SHALL BE 4" WIDE - 12 GAUGE STEEL, COLOR BLACK. CONTRACTOR SHALL LAYOUT EDGING FOR APPROVAL AND INSTALL PER MANUFACTURERS RECOMMENDATIONS.
- 20. PLANTS SHALL BE WATERED BEFORE AND AFTER PLANTING IS COMPLETE. ALL TREES MUST BE STAKED, FERTILIZED AND MULCHED AND SHALL BE GUARANTEED TO EXHIBIT A NORMAL GROWTH CYCLE FOR AT LEAST ONE (1) FULL YEAR FOLLOWING PLANTING. ALL DISEASED, DAMAGED, OR DEAD MATERIAL SHOWN ON THE SITE PLAN SHALL BE REPLACED BY THE END OF THE FOLLOWING GROWING SEASON.
- 21. APPLICATIONS OF FERTILIZER BEYOND THE INITIAL TOPSOIL AND SEEDING SHALL BE A FERTILIZER WITH NO PHOSPHOROUS.
- 22. CONTRACTOR SHALL INFORM LANDSCAPE ARCHITECT OF ANY FOUND DISCREPANCIES IN WRITING PRIOR TO INSTALLATION. 23. PLANTING SOIL AND MULCH INSTALLATION IS INCIDENTAL TO LANDSCAPE PAY ITEMS.

#### PLANTING MIXTURE NOTES

- PART COMPOST. ADD FERTILIZER AT THE QUANTITY AS RECOMMENDED BY THE MANUFACTURER. PLANTING MIXTURE SHALL BE FREE FROM, STICK, STONES, SOD CLODS, OR OTHER MATERIAL WHICH MIGHT LEAVE POCKETS AROUND THE ROOTS.
- 2. TOPSOIL
  2.1. TOPSOIL SHALL BE FERTILE, FRIABLE, SANDY CLAY LOAM WITHOUT ADMIXTURE OF SUBSOIL. TOPSOIL IS TO BE FREE OF GLASS, STONES GREATER THAN ONE (1) INCH IN ANY DIMENSION, WEEDS, UNDESIRABLE GRASSES AND OTHER EXTRANEOUS MÁTERIALS.
  - TOPSOIL SHALL HAVE THE FOLLOWING RANGE OF VALUES: SOLUBLE SALTS 500 PPM MAX
    ORGANIC CONTENT 5% TO 30%
    SILT CONTENT 35% TO 50%
  - CLAY CONTENT 5% TO 10% DELETERIOUS MAT'L\* 5% MAX \*ROCK, GRAVEL, STONE, STICKS, ROOTS, SOD, ETC.
- 2.2. TOPSOIL IS TO BE FINAL SCREENED THRU A 5/8" MAXIMUM MESH SCREEN PRIOR TO DELIVERY TO THE PROJECT SITE. ENGINEER SHALL REVIEW SOURCE AND FINAL SCREEN RESULTS PRIOR TO RELEASE OF TOPSOIL. CONTRACTOR SHALL SUBMIT A CERTIFIED ANALYSIS OF THE TOPSOIL FROM EACH SOURCE TO THE ENGINEER. TOPSOIL SHALL BE PLACED IN 4-INCH MINIMUM THICKNESS THROUGHOUT.
- 3. SAND FOR PLANTING MIXTURE SHALL BE CLEAN, MEDIUM-COARSE, UNGRADED SAND CONFORMING TO ASTM C3 FOR FINE AGGREGATES.
- 4. COMPOST SHALL BE COMPOSTED PINE BARK FINES OR OTHER HIGH-LIGNIN BARK FROM SPRUCE, FIR, OR OTHER CONIFERS.

### LANDSCAPE SCHEDULE

	SYMBOL	CODE	BOTANICAL NAME	COMMON NAME	SIZE	<u>QTY</u>	SPACING
TREES	$\bigcirc$	CC	CARPINUS CAROLINIANA	AMERICAN HORNBEAM	2.5" CAL.	2	PER PLAN
	$\odot$	FG	FAGUS GRANDIFOLIA	AMERICAN BEECH	2.5" CAL.	2	PER PLAN
SHRUBS	$\odot$	СО	CEPHALANTHUS OCCIDENTALIS	COMMON BUTTONBUSH	#3	24	PER PLAN
	$(\nabla)$	РО	PHYSOCARPUS OPULIFOLIUS	COMMON NINEBARK	#3	22	PER PLAN
	$\bigcirc$	ST	STAPHYLEA TRIFOLIA	AMERICAN BLADDERNUT	#3	4	PER PLAN
PERENNIALS	$\bigoplus$	AF	ATHYRIUM FILIX-FEMINA	LADY FERN	#1	60	PER PLAN
	****	CL	CHASMANTHIUM LATIFOLIUM	NORTHERN SEA OATS	#1	60	PER PLAN
	PATTERN	TYPE	2	QUANTITY			
SEED MIXES		RAINGAF	RDEN	1,706 S.F.			
	+ + + + + + + + + + + + + + + + + + + +	SHORT V	VOODLAND	11,397 S.F.			

SHORT WOODLAND ECO-TURF LOW MAINTENANCE FESCUE 4,738 S.F.



 $\Phi$ p L O 0

0

MDNR Review 8/19/24 90% Review 12/20/24 ( 01/16/25

CSJ200101D

-2.1